ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notification dated 4th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 8th May 1933, for Restoration of Kakaramanahalli, Basavegowdankere R. No. 208 of Closepet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1934.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.

3 Tenders should be submitted on printed forms which, may be obtained from the Executive Engineer. They should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 as earnest money and be superscribed "Tender for Restoring Kakaramanahalli, Basavegowdankere R. No. 208 of Closepet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender, will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted in the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotations quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily be rejected.

Abstract estimate for the Restoration of Kakaramanahalli, Basavegowdankere, Minor Tank R. No. 208 of Closepet Taluk.

No.	Items of work	Per	Quantity
	Bund R. L. 56·50.		
1	Clearing jungle, ant-hills and cutting grips, etc.	Grade	14
2	Earthwork to bund including watering and tamping, etc., complete.	C.yd.	4816
3	Turfing	S.yd.	2894
4	New stone revetment	C.yd.	633
5	Gravel backing to revetment	,,	211
6	Resetting old stone revetment with new jelly, etc., complete ...	,,	50
7	Providing new grade stones, cutting figures painting, etc. ...	Each.	15
8	Providing Index stones do	,,	15
9	Do B. M. stones do	,,	2
10	Do Registered No. stone do	,,	1
11	Do Gauge stones	,,	1
	Waste weir at Right R. L. 53·00, 54' ft.		
1	Earthwork excavation	C.yd.	26
2	Burnt stone slabs of 6" thick roughly dressed and fixed, including cement pointing.	S.ft.	77
3	Burnt brick in surki mortar	C.ft.	309
4	Surki mortar plastering	Sqr.	0·18
		C.yd.	12

Notification dated 7th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th April 1933 for "Restoring the channels from Aralamallige Tank of Dodballapur Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. They should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 as earnest money and be superscribed "Tender for Restoring the channels from Aralamallige Tank, Doddaballapur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted in the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc. that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotations quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily be rejected.

Abstract estimate for Restoring channels from Aralamallige Tank R. No. 241 of Dodballapur Taluk.

No.	Item of work	Per	Quantity
	Hikkal Channel.		
1	Jungle clearing including removal of prickly pear, etc., complete	Syd.	2,000
2	Earthwork including watering and tamping with ½ a mile lead	C.yd.	590
3	Do to bank ordinary soil without lead ...	,,	1,390
4	Do cutting used to bund ordinary soil ...	,,	100
5	Lead for above cutting used to bank with watering and tamping	,,	100
6	New stone revetment with jelly backing and wedging ...	,,	205
7	Turfing	S.yd.	2,426
8	Providing bed grade stone	Each	22
9	Fixing demarcation stone	,,	44
	Constructing Madabois as per Type design.		
1	Earthwork excavation and forming	C.yd.	5
2	Stone jelly surki concrete	C.ft.	2
3	Burnt brick in surki mortar	,,	26
4	Surki plastering	Sqr.	0·41
5	Cast iron pipe including carting and fixing	R.ft.	9

No.	Item of work	Per	Quantity
	Constructing Relieving weir.		
1	Earthwork excavation	C.yd.	17
2	Stone jelly surki concrete	C.ft.	88
3	Burnt brick in surki mortar	,,	138
4	Burnt stone slabs 6" thick roughly dressed including cement pointing.	S.ft.	50
5	Surki plastering	Sqr.	0·79
6	Rough stone work new with jelly backing and wedging ...	C.yd.	16
	Constructing a super passage at C. S. No. 30.		
1	Earthwork excavation	C.yd.	49
2	Stone jelly concrete in surki mortar	C.ft.	168
3	Burnt brick in surki mortar	,,	1,435
4	Burnt stone slabs one line dressed and fixing including cement pointing.	S.ft.	388
5	Plastering with surki mortar	Sqr.	9·55
6	Pointing with cement	,,	1·10
7	Rough stone work new with jelly backing and wedging ...	C.yd.	37

Abstract Notification dated 26th March 1933.

The attention of public is invited to the notification inviting tenders for the Construction of a New Tank near Kannaikan Agrahara Village of Anekal Taluk, published on pages 379 and 380, Part VI of the *Mysore Gazette*, dated 6th April 1933. The last date for the receipt of tenders is 24th April 1933 (at 2 P.M.) and earnest money to be deposited is Rs. 250.

H. F. MARKER,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

No. 1688, *dated 25th March* 1933.

The attention of the public is invited to the Notification dated 22nd March 1933, calling for tenders for "Improving the Water Supply Scheme to the Robertsonpet" published on pages 378 and 379, Part VI of the *Mysore Gazette*, dated 6th April 1933. The last date for receipt of tenders is 15th April 1933.

B. R. GARUDACHAR,
Executive Engineer.

TUMKUR DIVISION

Abstract Notification, dated 28th March 1933.

Subject.—

Opening a road from Gubbi to Chitnahalli or Chandrasekharapura in Gubbi Taluk.

Attention of the public is drawn to the notification calling for tenders for the above work in page 382 and 383, Part VI of the *Mysore Gazette*, dated 6th April 1933.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up-to 3 P.M. of 26th April 1933.

3. An earnest money of Rs. 700 should accompany the tender.

N. G. KRISHNA IYENGAR,
Executive Engineer,

KOLAR DIVISION.

Notification dated 12—13th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 2nd May 1933, for Restoring Mallandahally Doddakere, Registered No. 151—877 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1934.